




Financial Offer: Rehabilitation and maintenance work in AlHol and Roj Camps in North East Syria

العرض المالي : اعمال صيانة واعادة تأهيل في مخيمي الهول و روج في شمال شرق سوريا

#	Items Description	Qty	Unit	Unit Cost (US\$)	Total Cost (US\$)	Remarks
A Rehabilitation the communal kitchens in Al-Hol and Roj camps camp.						
1.1	Supplying and installing tarpaulin cover and install it over the communal kitchens , as follows: 1- the weight :200 (+ - 10 gram)gram/m². 2- The fixing should be for the communal kitchens:(10.25m*5.85 m), tarpaulin cover should be fixed , by fixing rope width 2 cm, according to the instructions of engineer and attached drawings, - it will be install over the canvas if needed (mentioned in item 2) , and both layer (canvas and tarpaulin) will be fixed together, the price includes removing all the exist damaged tarpuline and plastic sheet, all the work should be done according to the site engineer instructions	9000	M2			Need Sample 
1.2	supplying and installing canvas cover and install it over the metal frame, as follows: 1- the weight :600 (+ - 20 gram) gram/m². The fixing should be : canvas should be fixed with the block wall from the four sites of the communal kitchens, by fixing rope width 2 cm, the price includes removing all the exist damaged canvas and plastic sheet, and all the work should be done according to the site engineer instructions	9000	M2			Need Sample 
1.3	Supply and implementaion material and construction hollow block for communal kitchens using masonry Block (40*20*15)cm, the price including the filling the space between blocks with cement mortar (1:3), with all necessary needs to complete the work according to the site engineer instrcutiions	600	M2			
1.4	Metal works for doors : Providing and installation metal door dimensions: 132 cm *200 cm using external frame from an angle line 4 cm * 4 cm, thickness 4 mm and internal from an angle line 3cm*3CM thick 3mm ,with horizontal beams 3 cm * 3 cm * 3 mm with metal sheet covering 1 mm thickness with paint and lock,hinges and all necessary, all the work should be done according the draw and to the site engineer instructions	182	M2			
1.5	Metal works for windows: Provide and install metal windows dimensions: 120cm * 100 cm Using external metal frame dimensions 4 cm * 4 cm thickness 4 mm and internal from an angle line 3cm*3cm thick 3mm on two open gate with glass thickness 4 mm with paint and the lock,hinges and all necessary. -providing a protection metal mesh consist from metal rectangle tubes 3 cm x cm thickness 2 mm welded on the outer frame and the group welded to the outer frame of the window and a horizontal beam in the middle of the metal bars 3 cm * 2 cm thickness 2 mm , the price includes painting works with one layer of anti rust paint and two layer of oil paint with all necessary needs to complete the work per site engineer instructions	120	M2			
1.6	Provide and install glass for windows thickness 4mm with fixing using cylicone, the price including remove the old broken windows glass,The work to be done according to instructions of the site engineer.	72	M2			
1.7	Cooking table: Provide and install the Cooking table for communal kitchen using the concrete block 40*20*15 cm for leg dimention (60cm*90cm) and kitchen stone dimention (100cm*60* 5cm),The work to be done according to instructions of the site engineer.	140	No			
1.8	Providing materials and manpower beam for casting plain concrete 250kg/m3 around outer concrete base for communal kithchen by dimention (20*30)cm and length not less from 31 M.l for each kitchen, the work to be done according to the instruction of site engineer.	150	M.l			

Financial Offer: Rehabilitation and maintenance work in AlHol and Roj Camps in North East Syria

العرض المالي : اعمال صيانة واعادة تأهيل في مخيمي الهول و روج في شمال شرق سوريا

#	Items Description	Qty	Unit	Unit Cost (US\$)	Total Cost (US\$)	Remarks
1.9	Tent metal roof frame: Provide and install upper part of communal kitchen from cylindrical section using pipe 1 inch and not less than 2 mm, by height of 1.30 cm, the price including fixing the pipe section together via proper methods (via welded metallic rings and tube 2*2 *0.2cm by length not less from 1.5 m) and all necessary works paint (primary & oily paint), the work to be done according to the instruction of site engineer.	150	No			
Total Amount in US\$ for (A)						

B	Maintenace road in Al Hol and Roj Camps					
2.1	BASE WORKS (Crushed Gravel): Providing materials, all required machines and Equipment's for laying a screened crushed gravel by grader above compacted existing layer with minimum 10cm thickness after compaction in one layer, with watering and . The layer should have a slope of 2-2.5%, either to do chamber or side slope (would be determined in the site according to the location) and the Debris must be disposed of off-site in a manner approved by the camp management, All work must comply with technical instructions of engineer.	25,500	M2			Need Sample
2.2	Provision materials and hiring manpower using hollow block (15x20x40)cm, to rehabilitate and build walls for tents of different quantities, in multiple locations and at different heights, as directed by the site engineer by using cement and sand mortar 1:3 for all block works construction and filling joints, with all nacassry need to complete the work. Note: The incoming quantity is consumed (by building above the concrete base for the family tent, and the lack of hollow block is compensated in some of the walls that were previously constructed and in some locations).	600	M2			
Total Mount in US\$ for (B)						

C	Maintenance and replacement of Caravans / Blumont sites.(HOL and Roj)camps					
3.1	Caravan floor works: Provide and install glued PVC floor covering in a thickness not less than 2 mm for a floor with all Accessories (Rail of caravan edges), the price including remove the old one and relocating them to selected locations from the local administration, the price including fixing the metal floor on the tube mesh using welding and screws, The work to be done according to instructions of the site engineer.	250	M2			

Financial Offer: Rehabilitation and maintenance work in AlHol and Roj Camps in North East Syria**العرض المالي : اعمال صيانة واعادة تأهيل في مخيمي الهول و روج في شمال شرق سوريا**

#	Items Description	Qty	Unit	Unit Cost (US\$)	Total Cost (US\$)	Remarks
3.2	Provide and install PVC plastic door with all necessary (locks, hinges.....etc)all works should be done according to the site engineer instrution	15	No			
3.3	Provide and install PVC plastic windows with all necessary (4mm thick glas, locks, hinges.....etc)all works should be done according to the site engineer instruction	20	M2			
3.4	Provide and install glass for windows thickness 4mm with fixing using cylicone, the price including remove the old broken windows glass,The work to be done according to instructions of the site engineer.	70	M2			
Total Amount in US\$ for (C)						

Total Amount in US\$ for (A+B+C)	
----------------------------------	--

NOTE:

1. Our organization has the right to reject any above mentioned items when delivered by the contractor in case if the quality of the item is not meet our spesifications and required quality and to request a better quality.
2. Our organization is not bound to buy the whole quantity mentioned in the Financial Offer.
3. Our organization is not bound to contract with one company and can split the award between one or more companies.
4. The Service must delivered to Al-Hol and Roj Camps as per the instruction of Our Organization's Supervisor .
5. The offered Price includes, transportation, loading & unloading and any other cost to deliver service to Al-Hol and Roj Camps.
6. The vendor must provide sample along with his offer for the items# (1.1, 1.2, 2.1) to (Hasaka Office in North East Syria) and the samples should meet the organization specification, otherwise his offer will be excluded.

ملاحظة:

1. يحق لمنظمتنا رفض أي عناصر مذكورة أعلاه عند تسليمها من قبل المقاول في حالة إذا كانت جودة العنصر لا تلي مواصفاتنا والجودة المطلوبة وأن يطلب جودة أفضل.
2. منظمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
3. المنظمة ليست ملزمة بأن تتعاقد مع شركة واحدة، ويمكن تجزئة العطاء بين أكثر من شركة.
4. يتم تقديم الخدمة المذكورة اعلاه في مخيمي الهول و روج وحسب خطة المقدمة من قبل مشرف المشروع للمنظمة .
5. الأسعار المقدمة يشمل جميع المصاريف من نقل و تحميل و تقديم الخدمة في مخيمي الهول و روج .
6. يجب على المورد تقديم عينة (نموذج) مع عرضه للمواد (1.1, 1.2, 2.1) في العرض المالي الى (مكتب حرك في شمال شرق سوريا) ،ويجب أن تفي العينات بمواصفات المنظمة، وإلا سيتم استبعاد عرضه.

Name of Signatory :

Name of Bidder :

Date of Signing :