


Financial Offer: Implementation of new Septic tank (s) Cover in Phase 5 in Al-Hol camp-NES. العرض المالي: تنفيذ أغطية خزان (خزانات) الصرف الصحي الجديدة في القطاع الخامسة في مخيم الهول شمال سرق سوريا						
#	Items Description	Unit	QTY	Unit Price (USD)	Total Price (USD)	PHOTO
1	<b><u>Septic tank (s) cover:</u></b> Provide and instal metallic cover for septic tank with different dimensions, using metallic tube of 6* 4 cm and 2 mm thickness, spaced at every 50 cm c/c in both direction. covered with a metal sheet of 2 mm thickness fixed to the tubes by screws and welding. Painting shall be two layers of anti-rust and two layers of oil painting for septic tank cover and frame, the price including de-sludge opening lid sized 40*40 cm , in addition all needs of (Locks, hinges,...etc). The work should be done according to the Design drawings and the instructions of the site engineer.	M²	2,880			

NOTE:

1. Our organization is not bound to buy the whole quantity mentioned in the Financial Offer.
2. Our organization is not bound to contract with one company and can split the award between one or more companies.
3. The Service must delivered to Al-Hol Camp, as per the instruction of Our Organization's Supervisor.
4. The offered Price includes transportation, loading & unloading, and any other cost to deliver and Implementation to Al-Hol Camp in North East SYRIA.
5. The company must submit approved site visit form and to be added to bid documents.
- 6.The company must specify at least two civil engineers to be on-site during the project implementation, with providing their safety requirements, minimum PPE for site staff including hard hat, vest, steel toe shoes.

ملاحظة:

1. منظمنا ليست ملزمة بسراء الكمية الكاملة المذكورة في جدول الكميات.
- 2.المنظمة ليست ملزمة بان تتعاقد مع سريكة واحدة، و يمكن تجزئة العطاء بسأكبر من سريكة.
- 3يتم التسليم للخدمات المذكورة اعلاه الى مخيم الهول في شمال سرق سوريا وحسب الخطة المقدمة من قبل مسرف المشروع للمنظمة .
- 4ألاسعار المقدمة جميع المصاريف من نقل و تحميل و التسليم والتنفيذ للمناطق المذكورة في مخيم الهول في شمال سرق سوريا .
- 5يجب على السريكة تقديم استمارة زيارة الموقع موقعة و معتمدة من قبل المهندس المسرف للمنظمة و يجب ارفاقها مع مستندات العطاء المقدم.
- 6يجب على السريكة تحديد ما لا يقل عن اثنس من مهندسس مدنيس ليكونوا في الموقع أثناء تنفيذ المشروع، مع توفر متطلبات السلامة الخاصة بهم ، والحد الأدنى من معدات الوقاية الشخصية لموظفي الموقع بما في ذلك قبعة صلبة ، وسرة ، وأحذية من الصلب.

Name of Signatory:.....

Title of Signatory:.....

Name of Bidder:.....

Signature & stamp:

Date of Signing:.....