



## Financial Offer: Providing General Maintenance in Tel Saman, Mahmoudly, Twihiniya and Newroz Camps - NES

العرض المالي: توفير صيانة عامة في مخيمات تل سمن, محمودلي, طويحينة ونوروز في شمال شرق سوريا

#	ITEM Description	Unit	Quantity	Unit Price (USD)	Total Price (USD)	Photos
<b>A-BOQ of General Maintenance in TSC</b>						
1	Maintenance of the roads in Tel Al-Samen camp by leveling the roads as needed and supplying crush stone and all machines needed (grader, roller, water tank, shovel .....etc) with workers if needed by spreading a layer of crushed stone at least 15 cm thick as needed, the price includes watering the site with good compacting, and remove the rubble and debris out of the camp to a location identified by the local authority, all the works should be done according to the site engineer instructions.	M <sup>3</sup>	2200			
2	Maintenance the drainage channels by provide workshop to crushing and rehabilitate the damaged rain drain channel with dim(20 cm thickness and 25 cm depth) two side with the base 20cm thick, and clean it from the rubble with provide all needs (framework, tools, workers, machines .....etc) to complete the work and remove the rubble out of the camp to a location identified by the local authority, all the works should be done according to the site engineer instructions.	ML	140			
3	Supply and provide a technical staff with all materials needed for re-casting the rain drain channels inside Tel Alsaman camp, for the damaged part (mentioned in item #2), the concrete of 300 kg /m <sup>3</sup> with section dia for the U shape as attached drawing, the channel will be (25cm for the walls and 15 cm for the base), and use nylon sheet under the concrete taking into account the tendencies of the channels with all necessary needed to complete the work and must the site comeback a clear as before, all the works should be done according to the instructions of the site engineer.	ML	140			
4	Maintenance of street drainage suitable for rain channel by excavate the channel path and remove all debris out of the camp to a location identified by the local authority and provide and extend pipes with dia. 8inch(best quality), with thick not less 4 mm, the price includes casting all sides of the pipe with thick not less 12cm and the roof with concrete 300kg/m <sup>3</sup> reinforced with BRC (15x15)cm, 8mm thick., all the works to be done according to the instructions of the site engineer	ML	60			
5	Maintenance of emollients of the rain chanel by remove the fence and crushing the damaged chanel and cleaning the site from all deris, and extend pipes with dia.10inch(best quality), with thick not less 4 mm, the price includes casting all sides of the pipe with thick not less 12cm and the roof with concrete 300kg/m <sup>3</sup> reinforced with BRC (15x15)cm, 8mm thick and the site comeback as before the work, all the works to be done according to the instructions of the site engineer.	ML	125			
6	Maintenance of complaints boxes as clear in the photo by re-painting it with 1 layer of anti-rust and 2 layer of oil paint, the price includes scrape all parts of the boxes and clean it by any liquid needed to be ready for the painting, all the works to be done according to instructions of the site engineer.	No	6			
7	provide and install metal stencil with 2 mm thick an indication to refer to the men's bathroom and the women's bathroom with dimensions of 40 * 40 cm all, the work should be done according to the site engineer instructions.	No	100			
8	Manhole maintenance: casting concrete cover (65X110)cm 15cm thick. to be reinforced with one layer of bar 12mm Dia. and spacing 15cm c/c both direction, all the works to be done according to the instructions of the site engineer.	No	20			

## Financial Offer: Providing General Maintenance in Tel Saman, Mahmoudly, Twihiniya and Newroz Camps - NES

العرض المالي: توفير صيانة عامة في مخيمات تل سمن, محمودلي, طويحينة ونوروز في شمال شرق سوريا

#	ITEM Description	Unit	Quantity	Unit Price (USD)	Total Price (USD)	Photos
9	Maintenance a damaged manhole be constructing a new one (80X80 )cm internal dimension, with walls thickness 20 cm, supply tools, machines, laborers and materials and excavations in all type of soil including rocky layers, with variable depth according to the ground level, reinforcement of one layer of 12mm dia. and 15cm c/c in both direction, the price included connect the old subline to the manholes and cleaning the site after completing all the works, all the works should be done according to the instructions of the site engineer.	No	2			
10	Manhole Covering: casting concrete slab (120X120)cm 15cm thick. to be reinforced with 1 layer of bar 12mm Dia. and spacing 15cm c/c,all the works to be done according to instructions of the site engineer.	No	2			
11	Provide and install a ceramic toilet seat western type of a high quality ,the price includes install and elbow,taps with all accessories needed to complete this work with a plastic washbasin with accesories needed and the samples should be checked and approved by site engineer before installation, with all necessary need to complete the work, all works should be done according to site engineer instructions.	No	3			
12	Prepare the site as needed and casting concrete base of the water tanks by dimentions ( 220*150)Cm , thick (10) cm , type of concrete 250 kg/m3 and laying thick nylon under the cast bases and make in one level with a surface smooth with considering slope for the water , the price include cleaning the ground from the rubble and all needed (framework, tools, workers ..... ) to complete this work , all the works to be done according to the drawing and instructions of the site engineer.	M <sup>3</sup>	16.5			
13	Provide materials and construct hollow blocks (15x20x40) cm thick block around the perimeter of the concrete base made of cement and sand mortor 1:3, cement 200 kg, the price including watering for three days at least and filling all space between the block with cement mortor,all the works to be done according to the drawing and instructions of the site engineer.	M <sup>3</sup>	9			
14	Prepare all materials with technical staff to casting the bases of latrines that damaged with dim(275*250)cm and thick 12cm with type of concrete 250 kg/m3,all the works should be done according to insructions of the site engineer.	M <sup>3</sup>	10			
15	Movement caravans (Dim 4.5 *1.20 m) to out of the camp by suitable crane(note: the distance between locations about 350 m), all the work should be done according to the site engineer instructions.	No	2			
16	Movement caravans (Dim3 * 3 m) to out of the camp by suitable crane(note: the distance between locations about 350 m), all the work should be done according to the site engineer instructions.	No	2			
Σ	<b>A-Total amount (USD)</b>					

## Financial Offer: Providing General Maintenance in Tel Saman, Mahmoudly, Twihiniya and Newroz Camps - NES

العرض المالي: توفير صيانة عامة في مخيمات تل سمن, محمودلي, طويحينة ونوروز في شمال شرق سوريا

#	ITEM Description	Unit	Quantity	Unit Price (USD)	Total Price (USD)	Photos
<b>B-BOQ of General Maintenance in MHD</b>						
1	wash basin maintenance: (25 wash basin) extending an 4 inch pipe from the wash basin to the manhole,So that the path of the pipe is excavated and encirclement it with fine sand and the soil is backfilled so that the depth of the top of the new pipe not less than 20 cm from ground surface, the price include breaking the sink drain nozzle, preparing a four-inch diameter strainer site without installing it and as well as cracking the pipe entry point with the manhole and plastering it with cement mortar 400 kg/m3. The price includes all the needs necessary to complete the work, such as pipe adhesive or piece of connection ... etc.The work should be according to site engineer instructure	ML	75			
2	Maintenance of sites in MHD camp by supplying crushed stone and all necessary machines (bobcat, graders, rollers, water tanks, shovel.....) and hiring labor if the site needs it in order to complete the leveling process by spread a layer of crushed stone. price Including hydration to complete the compacting process in sites that require and ,all work must be done according to the site engineer's instructions.	m3	400			
3	Replacement the damaged garbage containers with new one as barrel type,(100 liters-metal bins) dimension of barrel is 40 cm High ,57 cm diameter, with thick not less than 0.7mm , with fixing a belt as the top of container with two handel by welding for each container (the blet 3mm thick,3cm width) and painting one layer of anti-rust paint and two layer of oil paint, and the price include distribution it inside the camp with return the old bucket to Blumont warehouse , the work should be done according to the instruction of the site engineer.	psc	65			
4	Maintaining of the derainge path by supply and install all machine,tools,and materials hiring technical staff and excavation the soil for the channel path with section dia.(80*50)cm at more, the price includes all necessary works such as leveling the base of the excavated path and compacting works..ect. all the work should be done according to the site engineer instructions.	ML	261			
5	Supply and provide a technical staff with all materials needed for casting the rain drain channels inside MHD camp,(mentioned in pervious item ), the concrete of 300 kg /m3 with section dia for the U shape as attached drawing,the channel will be (25cm for the walls and 15 cm for the base), and use nylon sheet under the concrete taking into account the tendencies of the channels with all necessary needed to complete the work and must the site comeback a clear as before, all the works should be done according to the instructions of the site engineer.	ML	261			
Σ	<b>B-Total Amount (USD)</b>					

## Financial Offer: Providing General Maintenance in Tel Saman, Mahmoudly, Twihiniya and Newroz Camps - NES

العرض المالي: توفير صيانة عامة في مخيمات تل سمن, محمودلي, طويحينة ونوروز في شمال شرق سوريا

#	ITEM Description	Unit	Quantity	Unit Price (USD)	Total Price (USD)	Photos
<b>C-BOQ of General Maintenance inTWH</b>						
1	Maintenance of tank bases in TWH camp (33 bases) with a layer rough and soft another of mortar, caliber 350 kg/m <sup>3</sup> ,The price includes supply the needed material to complete work and execution plastering by hiring labor , as well as It also includes filling the gaps, if any , the work should be done according to the instruction of the site engineer.	m <sup>2</sup>	135			
2	Maintenance of sites in TWH camp by supplying crushed stone and all necessary machines (bobcat, graders, rollers, water tanks, shovel.....) and hiring labor if the site needs it in order to complete the leveling process by spread a layer of crushed stone. price Including hydration to complete the compacting process in sites that require and ,all work must be done according to the site engineer's instructions.	m <sup>3</sup>	400			
3	Replacement the damaged garbage containers with new one as barrel type,(100 liters-metal bins) dimension of barrel is 40 cm High ,57 cm diameter, with thick not less than 0.7mm , with fixing a belt as the top of container with two handel by welding for each container (the blet 3mm thick,3cm width) and painting one layer of anti-rust paint and two layer of oil paint, and the price include distribution it inside the camp with return the old bucket to Blumont warehouse , the work should be done according to the instruction of the site engineer.	psc	35			
Σ	<b>C-Total Amount (USD)</b>					

## Financial Offer: Providing General Maintenance in Tel Saman, Mahmoudly, Twihiniya and Newroz Camps - NES

العرض المالي: توفير صيانة عامة في مخيمات تل سمن, محمودلي, طويحينة ونوروز في شمال شرق سوريا

#	ITEM Description	Unit	Quantity	Unit Price (USD)	Total Price (USD)	Photos
<b>D-BOQ of General Maintenance in NRZ</b>						
<b>1</b>	<b>Communal kitchens</b>					
1.1	<b>Windows Glass:</b> Provide and install glass for windows thickness 3mm with fixing using silicone, the price including remove the old broken windows glass, The work to be done according to instructions of the site engineer	31	M <sup>2</sup>			
1.2	<b>Cooking table:</b> Provide and install the Cooking table for communal kitchen using the kitchen stone dimension (51*41* 5 cm),The work to be done according to instructions of the site engineer.	1	No			
<b>2</b>	<b>Toilet Caravan</b>					
2.1	<b>Toilet caravans:</b> Remove all sediment and cement mortar from the interior of the toilet rooms and corridors inside the toilet caravan(Each caravans have 4 toilet and 4 bathroom with 4 hand washing basin) using the labor and the appropriate tools to be clean and dry enough to extend the water-insulating silicon , all the work to be done according to the site engineer instructions	44	No			
2.2	<b>Silicon works inside toilet Caravans;</b> Supply and install silicon inside toilet caravans in interior of the toilet rooms and corridors and around the toilet squats and Foam from outside side and under caravans, In a manner that prevents the diversion of water to the metal floor of the caravan, the price including testing the all unites for 24 hours before handover to the Beneficiaries. all work to be done according to the site engineer instructions	44	NO			
2.3	<b>Doors work:</b> Provide and install aluminum latch lock for doors and remove the broken pieces. all work to be done according to the site engineer instructions	160	No			
2.3	<b>Doors work:</b> Providing and fixing aluminum work for doors fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions at top, bottom and sides with required rubber/ neoprene gasket etc., also Aluminum sections shall be smooth, rust free, straight, mitered and jointed mechanically wherever required including cleat angle, stainless steel screws, door hinges and latches, all complete as per site engineer instructions.	22	No			
2.4	<b>Doors maintenance work:</b> Provide and install Fiber sheet for internal aluminum doors in nessesary places according to the site engineer instructions.	7.5	M <sup>2</sup>			

## Financial Offer: Providing General Maintenance in Tel Saman, Mahmoudly, Twihiniya and Newroz Camps - NES

العرض المالي: توفير صيانة عامة في مخيمات تل سمن, محمودلي, طويحينة ونوروز في شمال شرق سوريا

#	ITEM Description	Unit	Quantity	Unit Price (USD)	Total Price (USD)	Photos
3	Fire extinguishing boxes					
3.1	Water source accessories; Supply and install water valve 2 inch copper type with all accessories (Male Stud Coupling, brass coupling,...etc.) to be ready to connecting the Fire extinguishing hose with water source. all the work to be done according to the site engineer instructions	5	No			
3.2	Fire extinguishing hose with Fire nozzle: Provide the fire extinguishing hose by length 24.5 m.l with brass coupling and Fire nozzle and install it inside the hose reels, all the work to be done according to the site engineer instructions.	4	No			
Σ	D- Total Amount (USD)					
Σ	Total A+B+C+D					

### NOTES:

- 1- All the items should be approved by our organization's field Staff.
- 2- Our organization is not bound to buy the whole quantity mentioned in the BOQ and will order as per need.
- 3- All the item quantities should be apply INCOTERM 2010 DDP (Delivery Duty Paid) to the mentioned locations.
- 4- Our organization is not bound to contract with one company and can split the award between one or more companies.
- 5- The delivery Locations are **Tel Semen, Mahmoudly, Twaihiniyah and Newroz Camps** in North-East Syria
- 6- The offered Prices includes, transportation, loading & unloading and any other cost to deliver and Implementation to locations mentioned in point(5) above in North East SYRIA

### ملاحظات:

- 1- يجب الموافقة على جميع الفقرات من قبل موظف الموقع لمنظمتنا.
- 2- منضمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات ويكون الطلب حسب الحاجة.
- 3- جميع كميات المواد يجب ان يكون (التسليم واجب مدفوعة) إلى المواقع المذكورة.
- 4- المنظمة ليست ملزمة بان تتعاقد مع شركة واحدة, ويمكن تجزئة العطاء بين أكثر من شركة
- 5- مواقع التوصيل موجودة في مخيمات (تل سمن, محمودلي, طويحينية ونوروز) في شمال شرق سوريا.
- 6- الأسعار المقدمة تشمل جميع المصاريف من النقل و التحميل و التسليم والتنفيذ للمناطق المذكورة في النقطة رقم (5) اعلاه في شمال شرق سوريا.

Name of Signatory: \_\_\_\_\_

Title of Signatory: \_\_\_\_\_

Name of Bidder: \_\_\_\_\_

Signature & stamp:

Date of Signing: \_\_\_\_\_