

FINANCIAL OFFER 2: Providing General Maintenance in Tel Saman, Mahmoudly, and Twihiniya Camps – NES**العرض المالي 2 : توفير صيانة عامة في مخيمات تل سمن, محمودلي, طويحينة في شمال شرق سوريا**

#	Description of the Items	Qty	Unit	Unit Cost (USD)	Total Amount (USD)
A- General Maintenance (Shelter) in TSC Camp					
1	Maintenance of the roads in Tel Al-Samen camp by leveling the roads as needed and supplying crush stone and all machines needed (grader, roller, water tank, shoveletc.) with workers if needed by spreading a layer of crushed stone at least 15 cm thick as needed, the price includes watering the site with good compacting, and remove the rubble and debris out of the camp to a location identified by the local authority, all the works should be done according to the site engineer instructions.	250	M³		
2	Maintaining and enhance of the identification office by supply all materials for sunshade to protect the IDPs from the raining water and sun rays, using grid of iron beam (rectangular pipe) 8X4X0.2 cm for the main structure and frame and for the external structure using (6X4)cm , the structure should be set on the grid of the columons using rectangular column 8*8 cm, 2mm thick ,fixed in pits 40x40x50 cm by concret 250 kg /m2 with plate 4 mm, consider the slope of the shade , and use extend Zinc sheet 0.7mm thick,the price including paint all the frames with anti-rust paint and two-layer of oil paint, the price includes all necessary works to complete the work,all the works should be done according to the instructions of the site engineer.	23	M²		
3	Maintaining and enhance of the warehouse by supply materials and hiring manpower to installing shelves in the warehouse with die, (40x90) cm the height 1.8 m, the space between each shelves 45cm, using iron section (4x4)cm 2mm thick for the main frame structure and columns, and (2x2)cm 1mm thick, for secondary structure as per engineer instructions, and the shelves should be covered with plate 1mm thick. the price includes all painting works with one layer of anti-rust paint and three layer of oil paint. with all needs to complete the work, all the work should be done according to the drawing and the site engineer instructions	10	No		
Σ	A-Total amount (USD)				
B- Maintenance works (Shelter) in MHD Camp					
Community Activities Tents					
1	Maintaining and enhance of the community activities tents by supply materials and install a wall of a hollow blocks 20*20*40 cm, mortar 160 kg/m3 , total of wall hight 200 Cm,the price includes implement columns of blocks by 40*40 cm every 3 mL along the wall line ,also the price includes implement concrete belt 250 kg/m3 above the wall along the wall line , all work should be done according to site engineer.	67	m3		
2	Maintaining and enhance of the community activities tents by Supply materials to implement two layer of plastering cement 300 kg/m3 (one rough and another soft) for wall in item #B1, all work should be done according to site engineer.	332	m2		

FINANCIAL OFFER 2: Providing General Maintenance in Tel Saman, Mahmoudly, and Twihiniya Camps – NES**العرض المالي 2 : توفير صيانة عامة في مخيمات تل سمن, محمودلي, طويحينة في شمال شرق سوريا**

#	Description of the Items	Qty	Unit	Unit Cost (USD)	Total Amount (USD)
Maintenance of road					
3	Maintenance of the roads in Mahmoudly camp by leveling the roads as needed and supplying crush stone and all machines needed (grader, roller, water tank, shoveletc.) with workers if needed by spreading a layer of crushed stone , the price includes watering the site with good compacting, and remove the rubble and debris out of the camp to a location identified by the local authority, all the works should be done according to the site engineer instructions.	400	M3		
Σ	B-Total amount (USD)				
C- General Maintenance (Shelter) in TWH Camp					
1	Maintaining of the Activities Tents by concrete slab Supply and install all materials and hiring technical staff to casting base with 12 cm thick , with 350 kg/m3 cement and reinforced 8mm 15 cm c/c , using naylon under the concret .with all necessary needs to complete the work according to the site engineer instructions.	15	M3		
2	Maintaining of the Activities Tents by Covering the tents (Dim 10.2*4 m + the arc in the roof) by using a two-layer covers, one of canvas cover of best quality and the second of plastic cover (450 g/m²) to isolate the water and protect the tent and must be the white color, The price includes all necessary needed of screws and sewing to complete the work (sewing the sides, sewing the roof and fix it on the land by ropes, open hole for doorwindows) all the work should be done according to the instruction of the site engineer .	126	m2		
3	Fence: Supply & Install chain link Fence (3.0 mm dia) of 1.8m height, the fence should be fixed with columns (2.5")dia. 1.8mm thick and struts every 3m (includes provide & install pipes), for the boundaries. the price includes install all columns in pits 40*40*50 cm with concrete and casting tie for the fence (Dim 20cm width, 20 cm high and for all the Fence) all the work should be done according to the details and site engineer instructions.	12	ml		
4	Maintenance the bottom part of the fence of by casting beam on the ground (Dim 20cm width, 20 cm high and for all the Fence)with 350 kg/m3 cement, all the work should be done according to the details and site engineer instructions.	115	ml		
5	Covering the tent (Dim 6*3.5 m + the arc in the roof) by using a one-layer covers plastic cover (450 g/m²) to isolate the water and protect the tent and must be the white color, The price includes all necessary needed of screws and sewing to complete the work (sewing the sides, sewing the roof and fix it on the land by ropes, open hole for doorwindows) all the work should be done according to the instruction of the site engineer .	210	m2		

FINANCIAL OFFER 2: Providing General Maintenance in Tel Saman, Mahmoudly, and Twihiniya Camps – NES**العرض المالي 2 : توفير صيانة عامة في مخيمات تل سمن, محمودلي, طويحينة في شمال شرق سوريا**

#	Description of the Items	Qty	Unit	Unit Cost (USD)	Total Amount (USD)
6	Maintenance of the roads in TWH camp by leveling the roads as needed and supplying crush stone and all machines needed (grader, roller, water tank, shoveletc.) with workers if needed by spreading a layer of crushed stone at least 15 cm thick as needed, the price includes watering the site with good compacting, and remove the rubble and debris out of the camp to a location identified by the local authority, all the works should be done according to the site engineer instructions.	250	M3		
7	Maintenance the air conditiner of guard caravan by cleaning the filters and re-filling with gaz 410 with check all maintenance needed(electrical maintenance ,connection Copper pipes - Pipe Isolationetc) all the works should be done according to the instructions of the site engineer.	5	Unit		
Σ	C-Total amount (USD)				
Σ	Total A+B+C+D amount (USD)				

NOTES:

- 1- All the items should be approved by our organization's site engineer.
- 2- The contractor should clean the site from all remenant and remaining materials after completing the work to the identified location by Local Administration.
- 3- Our organization is not bound to buy the whole quantity mentioned in the BOQ.
- 4- All the item quantities should be apply INCOTERM 2010 DDP (Delivery Duty Paid) to Tel Saman, Mahmoudly, and Twihiniya Camps in northeast Syria.
- 5- Our organization is not bound to contract with one company and can split the award between one or more companies.
- 6-The company must submit approved site visit form and to be added to bid documents.

ملاحظات:

- 1- يجب الموافقة على جميع الفقرات من قبل مهندس الموقع لمنظمتنا.
- 2- يجب على المقاول تنظيف الموقع من جميع المواد المتبقية والمخلفات المتبقية بعد الانتهاء من العمل ونقله إلى الموقع المحدد من قبل الإدارة المحلية.
- 3- منظمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
- 4- جميع كميات المواد يجب ان يكون (التسليم واجب مدفوعة) إلى مخيمات تل سمن, محمودلي, طويحينة في شمال شرق سوريا.
- 5- المنظمة ليست ملزمة بان تتعاقد مع شركة واحدة, و يمكن تجزئة العطاء بين أكثر من شركة
6. يجب على الشركة تقديم استمارة زيارة الموقع موقعة ومعتمدة من قبل المهندس المشرف للمنظمة و يجب ارفاقها مع مستندات العطاء المقدم.

Name of Signatory: _____

Title of Signatory: _____

Name of Bidder: _____

Signature & stamp:

Date of Signing: _____