




FINANCIAL OFFER: Maintenance of WASH Units in Tel Saman Camp in Northeast Syria

العرض المالي بصيانة وحدات مياه الصرف الصحي في مخيم تل السمن في شمال شرق سوريا

#	Description of the Items	Qty	Unit	Unit Cost (USD)	Total Cost (USD)	Photo
1	Supply and install all tools, materials and hiring technical staff to crushing the bases of latrines(concrete bases) with area 21.5m² and average thick 20cm ,for each 1 unit includes(4 latrine + hallway + stairs +PWD latrine with ramp + manhole) ,the price includes all necessary works need for cleaning the site and removing the debris and rubble out of the camp to location identified by local authority and also remove the metal frame of the latrine and put it in a safe place before crushing and the companys responsibility to take care of the steel structure of the latrine so they can reinstall it again, all the works should be done according to the site engineer instructions.	13	NO			
2	Provide and install a ceramic toilet seat(squat) eastern with elbow 4 inch of a high quality with all acceries needed and framework, tools, workersetc. to complete the work, all works should be done according to site engineer instructions.	52	NO			
3	Provide and install a ceramic toilet seat (western type) of a high quality, the price includes install the seat with elbow 4", taps and fix it on the ground with a needed screws and a good install with all acceries needed and framework, tools, workersetc. to complete the work and the samples should be checked and approved by site engineer before installation, all the works should be done according to site engineer instructions.	4	NO			
4	Provide and install all materials needed and hiring technical staff to re-install the old western seat with elbow, taps, and fix it on the ground with a needed screws and a good install with all acceries needed and framework, tools, workersetc. to complete the work and the samples should be checked and approved by site engineer before installation, all the works should be done according to site engineer instructions.	9	NO			
5	Provide and extend PVC drainage pipe 4" of a high quality for each squat with spreading fine sand around the pipe to connect the seats with the manholes with all acceries needed and framework, tools, workersetc. the price includes excavation works and backfilling work for the pipes, with all necessary needs to complete the work, according to site engineer instructions.	268	ML			
6	Provide and install for each 1 unit of latrine need (not less than 20 ML of PPR pipe 3/4 inch with all accessories needed for connecting(socket elbow,coupling socket,T-shape,brass female)...etc) + 6 taps with handheld hose plastic and ensure conncntg the main source of the water from the tanks,the price includes all works need to complete the works, all the works should be done according to the site engineer instructions.	13	NO			
7	Provide and install a plastic washbasin inside each unit of latrines by using profile 2*2cm as base welding on the structure of latrine with flexible hose drainage,the price includes extending pipe 2 inch to drain the washbasin water to the manhole(2 ML for each washbasin) with all accessories needed and connecting to complete the work,all the works should be done according to instnctions of the site engineer .	26	NO			
8	Provide and install stainless steel floor trap with 4" with elbow and extending pipe 3" to drain the washing water to the manhole,the price includes provide all accories needed for connecting and welding to complete the work (elbow 45 degree-elbow 90 degree-T shape-reducer....etc),all the works should be done according to instructions of the site engineer .	26	NO			
9	Excavation and removing debris, grading, clearance and excavation for the pipe path with dimension width not less than 0.6 m and the depth according to the slope in any type of soil & surfaces including rocky layers, etc. The work includes removal of old sewer pipes and old manholes rickets to the location identify by the local authority. All the works should be done according to the instructions of the site engineer.	530	ML			
10	PVC pipe: Supply and provide all materials needed and hiring technical staff to extend PVC pipes (10 inch) dia with thick ≥4mm of high quality for sewerage network, the price includes filling the path with fine sand under and around the pipes and the samples should be checked and approved by site engineer before installation, all the works should be done according to the instructions of the site engineer.	530	ML			
11	Backfilling Works: backfilling the channel path by natural soil with stones <2cm for layer in contact with the pipe, the last layer must be from crush stone with thickness 10cm and must the site comeback as before the work, all the works should be done according to the instructions of the site engineer.	530	ML			
12	Manhole: Maintenance a damaged manhole by constructing a new one (100X80)cm internal dimensions, with walls thickness 20 cm, supply tools, machines, laborers and materials and excavations in all type of soil including rocky layers, with variable depth according to the ground level and pipe slope, reinforcement of 2 layer of 10mm dia. and 15cm c/c in both direction, the price includes connect the new subline to the manholes and cleaning the site after completing the works, all the works should be done according to the instructions of the site engineer.	20	NO			
13	Manhole Covering: casting concrete slab (120X140) cm 12cm thick. to be reinforced with 1 layer of bar 10mm Dia. and spacing 15cm c/c, all the works to be done according to instructions of the site engineer.	20	NO			
14	Manhole: provide materials and hiring technical staff to casting a new manhole (50X30)cm internal dimensions, with walls thickness 15 cm, supply tools, machines, labors and materials and excavations in all type of soil including rocky layers, with variable depth according to the ground level and pipe slope, the price includes connect the new subline to the manholes and cleaning the site after completing the works, all the works should be done according to the instructions of the site engineer.	26	NO			
15	Manhole Covering: casting concrete slab (80X60) cm 12cm thick. to be reinforced with 1 layer of bar 10mm Dia. and spacing 15cm c/c, all the works to be done according to instructions of the site engineer.	26	NO			
16	Concrete works : provide all materials needed and hiring technical staff to casting bases of latrines with dimensions(5.35*3.20 for eastern latrines +1.6*2.20 for PWD latrine + 2*1m for ramp) with thick not less than 15cm included each 1 unit (4 eastern latrine + hallway +PWD latrine with ramp) with concrete 250kg/m³ ,the price includes provide all tools needed and framework to complete the works and make sure the surface should be smooth and consider slope of the water, all the works should be done according to the site engineer instructions.	13	NO			

17	Provide all materials needed and hiring technical staff to re-welding the metal structure of the latrine wich removed in the item #1 by fixed plates 2mm 15*15cm with concrete casted, the work includes fixed the structure on the same location with same details as before fixed, with all necessary needs to complete the work be done according to instructions of the site engineer.	13	NO			
18	provide and install metal stencil with 2 mm thick an indication to refer to the men's latrines and the women's latrines with dimensions of 40 * 40 cm ,all the works should be done according to the site engineer instructions.	26	NO			
19	Providing and spreading a clean layer of crushed stone after completed the works with thick not less than 10cm, the price includes hiring all machines needed and workers for spreading, all the works should be done according to instructions of site engineer.	100	M³			
Total Amount (USD)						

NOTES:

- 1- All the items should be approved by our organization's site engineer.
- 2- The contractor should clean the site from all remenant and remaining materials after completing the work to the identified location by Local Administration.
- 3- Our organization is not bound to buy the whole quantity mentioned in the BOQ.
- 4- All the item quantities should be apply INCOTERM 2010 DDP (Delivery Duty Paid) to the mentioned locations.
- 5- Our organization is not bound to contract with one company and can split the award between one or more companies.
- 6-The company must submit approved site visit form and to be added to bid documents.

ملاحظات:

- 1- يجب الموافقة على جميع الفقرات من قبل مهندس الموقع لمنظمتنا.
- 2- يجب على المقاول تنظيف الموقع من جميع المواد المتبقية والمخلفات المتبقية بعد الانتهاء من العمل ونقله إلى الموقع المحدد من قبل الإدارة المحلية.
- 3- منظمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
- 4- جميع كميات المواد يجب أن يكون (التسليم واجب مدفوعة) إلى المواقع المذكورة.
- 5- المنظمة ليست ملزمة بأن تتعاقد مع شركة واحدة, و يمكن تجزئة العطاء بين أكثر من شركة
- 6 يجب على الشركة تقديم استمارة زيارة الموقع موقعة ومعتمدة من قبل المهندس المشرف للمنظمة و يجب إرفاقها مع مستندات العطاء المقدم.

Name of Signatory: _____

Title of Signatory: _____

Name of Bidder: _____

Signature & stamp:

Date of Signing: _____