






Financial Offer: Provide Measurement tools for site engineer for Al-Hol camp in North East SYRIA

العرض المالي : توفير أدوات قياس لمهندسين موقع في مخيم الهول في شمال شرق سوريا

#	Description of the Items	Pictures	Unit	Qty	Unit Cost (USD)	Total Cost (USD)
1	supply a Vernier caliper(electronic) very good quality and should approved by the site engineer		piece	4.00		
2	supply a scientific calculator(Casio fx-991 ES PLUS) should approved by the site engineer		piece	5.00		
3	supply a metallic Measure Tape(7 m) should approved by the site engineer		piece	10.00		
4	supply Measure Tape (50 m) should approved by the site engineer		piece	4.00		
5	supply Bubble level 0.5 m should approved by the site engineer		piece	5.00		
6	supply an aluminum screeding level 2 m straight edge box 100*40 mm, should be approved by site engineer		piece	4.00		
7	supply a plumb bob with a steel head more than 200 gr, and nylon thread ,should be approved by site engineer.		piece	4.00		
8	supply a measuring wheel good quality unit to measure meter		piece	1.00		
9	supply slump cone test equipment, the cone Size: 100*200*300mm, use metallic plate of 1.5 mm for the cone and base, the base 30*40cm with handles,in addition metallic scoop, metallic ruler, and metallic stick		piece	1.00		
10	Providing a device for measuring the salinity of the water (salinometer) with all the necessary materials, it must be approved by the site engineer.		piece	2.00		
11	Provide the hammer device (for measuring the compressive strength of cast concrete) with all the necessary accessories, and it must be approved by the site engineers.		piece	1.00		

Financial Offer: Provide Measurement tools for site engineer for Al-Hol camp in North East SYRIA						
العرض المالي : توفير أدوات قياس لمهندسين موقع في مخيم الهول في شمال شرق سوريا						
12	Digital clamp avometer :- Max.LCD display 1999 Rang selection manual- AC voltage 1000v ± 1.0%- AC current 1000A ± 2%- DC voltage- Resistance 200Ω/2MΩ ±1.0% - Continuity test yes - Diode test yes- Data hold yes - Back light yes - Temperature: from -40 to +1000°C- Power: 3V bat. (2x AAA) - Digital clamp multimeter		piece	1.00		
13	Voltage tester -220 to 240 VAC		piece	1.00		
14	Toolbox : Portable plastic box (50x25x25) cm		piece	1.00		
15	providing a high-quality engineering safety kit best type available in the markets, consist of Boots, helmet,gloves, vest and winter reflective jacket, all the materails should be approved by site engineer.		kit	9.00		
Grand Total cost in USD						

- NOTE:
- Our organization is not bound to buy the whole quantity mentioned in the Financial Offer.
 - Our organization is not bound to contract with one company and can split the award between one or more companies.
 - The price must include the delivery of materials and levelling processes to Al-Hol Camp/ Al-Hassaka.
 - The offered Price includes, transportation, loading & unloading and any other cost to distribute as per the locations/quantity required.
 - Any Items (Goods or Materials) to be proposed shall not be manufactured or produced by any restricted country (Iran, Libya, Cuba , and North Korea).

ملاحظة:

1. منظمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
2. المنظمة ليست ملزمة بان تتعاقد مع شركة واحدة، و يمكن تجزئة العطاء بين أكثر من شركة.
3. السعر يجب ان يتضمن توصيل المواد لمخيم الهول.
4. الاسعار المقدمة جميع المصاريف من نقل و تحميل و توزيع للمواقع المطلوبة.
5. أي مواد او معدات مقدمة للمنظمة ذو منشاء او انتاج من (إيران وليبيا وكوبا وشمال كوريا) غير مقبولة وبناء عليها سيتم رفض العرض المقدم.

Name of Signatory:.....

Title of Signatory:.....

Name of Bidder:.....

Signature & stamp:

Date of Signing:.....