




## Financial Offer: General Maintenance in Mahmoodly Camps /NES

العرض المالي: صيانة عامة في مخيم المحمودلي/ شمال شرق سوريا

| #                                       | Items Description  | الوحدة | الكمية | Photo  | سعر الوحدة بالدولار الأمريكي (USD) | السعر الإجمالي بالدولار الأمريكي |
|---|--|--------|--------|--|------------------------------------|----------------------------------|
|   |  | Unit   | QTY    | صور  | Unit Price (USD)                   | Total Price (USD)                |
| Warehouse                               |  |        |        |  |                                    |                                  |
| 1                                       | Maintaining and enhance of the Blumont's warehouse tents by supply materials and install a wall of a hollow blocks 20*15*40 cm, mortar 160 kg/m3 , total of wall hight 200 Cm,the price includes implement columns of blocks by 40*30 cm almost every 3 mL along the wall line ,also the price includes implement concrete belt 250 kg/m3 , 6 cm hight above the wall along the wall line , all work should be done according to site engineer.  | m3     | 29     |    |                                    |                                  |
| 2                                       | Maintaining and enhance of the warehouse tents by Supply materials to implement two layer of plastering cement 300 kg/m3 (one rough and another soft) ,taking into consideration that Window openings don't count, all work should be done according to site engineer.   | m2     | 129    |  |                                    |                                  |
| Camp Sites                              |  |        |        |  |                                    |                                  |
| 3                                       | Maintaining of the IDPs tents yard ( by supply materials and install a wall of a hollow blocks 15*20*40 cm, using cement mortar 1:3 to fill the joints between the Blocks, total of wall hight 63 Cm, and fill the partial damaged block as in the drawing with cement mortar, all work should be done according to site engineer  | m3     | 12     |    |                                    |                                  |
| 4                                       | Supply materials and implement concrete belt (12 cm hight) - 250 kg/m3 above the conceete block walls, the price includes all necessary needs to complete the work according to the site engineer instructions.  | ML     | 34     |  |                                    |                                  |
| 5                                       | Maintenance of the roads in MHD camp by leveling the roads as needed and supplying and spread crush stone on the road, using equivalent machines needed (grader, roller, water tank, shovel .....etc.) with workers if needed the spreading of crushed stone layer least 12 cm thick as needed, the price includes watering the site with good compacting, and remove the rubble and debris out of the camp to a location identified by the local authority, all the works should be done according to the site engineer instructions. | m3     | 400    |  |                                    |                                  |
| Community mobilization activities tents |  |        |        |  |                                    |                                  |
|   | Maintaining and enhancing of the community activities tents by supply materials and casting concrete floor, thickness not less than 8 cm, taking into account the appropriate slop to drain cleaning water, (250 kg/m3) with all necessary needs to complete the work, according to instruction of site engineer.  | m3     | 29     |  |                                    |                                  |
|   | Maintaining and enhance of the community activities tents by Supply materials to implement two layer of plastering cement 300 kg/m3 (one rough and another soft) ,taking into consideration that Window openings don't count, all work should be done according to site engineer.  | m2     | 290    |  |                                    |                                  |
| Grand Total in USD                      |  |        |        |  |                                    |                                  |

### NOTE:

- Our organization is not bound to buy the whole quantity mentioned in the Financial Offer.
- Our organization is not bound to contract with one company and can split the award between one or more companies.
- The price must include the delivery of materials to MHD Camps in Northeast Syria
- The offered Price includes, transportation, loading & unloading and any other cost to distribute as per the locations/quantity required.
- The company must submit an approved site visit form, and to be added to bid documents

### ملاحظة:

- منظمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
- المنظمة ليست ملزمة بان تتعاقد مع شركة واحدة، و يمكن تجزئة العطاء بين أكثر من شركة.
- السعر يجب ان يتضمن توصيل المواد الى مخيم محمودلي في شمال شرق سوريا
- الاسعار المقدمة مع جميع المصاريف من نقل و تحميل و توزيع للمواقع المطلوبة.
- يجب على الشركة تقديم استمارة زيارة الموقع موقعة ومعتمدة من قبل المهندس المشرف للمنظمة و يجب ارفاقها مع مستندات العطاء المقدم.

**Financial Offer: General Maintenance in Mahmoodly Camps /NES**

العرض المالي: صيانة عامة في مخيم المحمودلي / شمال شرق سوريا

| # | Items Description | الوحدة | الكمية | Photo | سعر الوحدة بالدولار<br>الامريكي (USD) | السعر الاجمالي بالدولار<br>الامريكي |
|---|-------------------|--------|--------|-------|---------------------------------------|-------------------------------------|
|   |                   | Unit   | QTY    | صور   | Unit Price<br>(USD)                   | Total Price (USD)                   |

Name of Signatory:.....

Title of Signatory:.....

Name of Bidder:.....

Signature & stamp:

Date of Signing:.....