








FINANCIAL OFFER 1: Rehabilitation of Electrical Network in Tal Saman Camp in Northeast Syria.

العرض المالي 1: إعادة تأهيل الشبكة الكهربائية في مخيم تل سمن في شمال شرق سوريا

BoQ for Rehabilitation of Electrical Network in Tal AL Saman Camp							
#	Item description	Unit	Qty	Unit Price (USD)	Total Price (USD)	Photo	Sample Required
1	Provide workers with all tools needed to remove all the old, random and damaged electricity network inside the camp included (cables, breakers panels, switches.....etc., all the works should be done according to the details and site engineer instructions.	L.S	1				
2	Provision and installation metal pole 3.0 meter (8x8) cm thickness 2 mm, with metal plate (30x40) cm thickness 2mm should be welded to the pole with anti-rain protection (Sunshade) as drawing attached, with Two layer of anti-rust paint and Two layer of oil paint, all the works should be done according to the details and site engineer instructions.	NO.	102				
3	Excavation, Provision and installation concrete base rate cement 250kg/m3 for metal pole bases Dim(50x50x50cm), including backfilling, removal of surplus material, all the works should be done according to the details and site engineer instructions.	NO.	102				
4	Provision and installation metal circuit breakers panel with suitable lock and rain cover and painted accommodate to not less than 10 breakers ,the price includes provide a piece of wood (30x40)cm thickness 18mm which will be fixed between the metal plate and the metal breaker panel, with all accessories needed to complete the work ,all the works should be done according to the details and site engineer instructions .	NO.	102				
5	Provision and installation Electrical circuit breaker- MCB - thermal magnetic operation-50 A - tow pole(1 ph +N) - type C - best quality with all accessories for installation inside metal panel ,all the works should be done according to the details and site engineer instructions.	NO.	102				YES
6	Provision and installation electrical circuit breaker- MCB - thermal magnetic operation-6A - one pole(single phase) - type C - best quality with all accessories needed for installation inside metal panel ,all the work should be done according to the details and site engineer instructions.	NO.	770				YES
7	Provision and installation electrical stranded Cable (2x6) mm² Cu/ PVC shield and PVC filling -best quality with all accessories needed for installation between the public network and each metal breakers panel, the price includes extend wire link metal 3mm to tighten the cable all the works should be done according to the details and site engineer instructions.	M.L	2700				YES
8	Provision and installation electrical stranded Cable (2x2.5) mm² Cu/ PVC shield and PVC filling - best quality with all accessories needed for installation between the metal breakers panel and each tent, the extension is underground to a depth of not less than 15 cm and the cable is placed into a strong plastic pipe not less than 16mm dia. with all necessary works, accessories, and all excavation and backfilling works, all the works should be done according to the details and site engineer instructions .	M.L	7780				YES
9	Provision and installation full electrical outlet socket, 16 A , 250V ,next to the tent door with the plastic mounting box (external), mounting plate and cover plate, all the sockets must be of the "Schuko" type, the price includes extend the needs cables which should be (2x2.5)mm² Cu/ PVC inside the tent, all cables are fixed to structure of the tent inside plastic pipe not less than 16mm and to be fixed with plastic belts, with all needed works, materials and accessories, all the works should be done according to the details and site engineer instructions.	NO.	770				YES
10	Provision and installation LED lamp 9 watts (best quality) with plastic holder, the price includes extend the needed cable which should be (2x1.5)mm² Cu/ PVC with switch ,and connect the lamp to the operating switch, all cables should be fixed to the structure of the tent inside plastic pipe not less than 16mm and to be fixed with plastic belts, with all needed works, materials and plastic thermal (Jenkesion) with 2.5 mm size accessories, all the work should be done according to the details and site engineer instructions.	NO.	770				YES
Total Cost (USD)							

NOTES:

- 1- All the items should be approved by our organization's site engineer.
- 2- The contractor should clean the site from all remenant and remaining materials after completing the work to the identified location by Local Administration.
- 3- Our organization is not bound to buy the whole quantity mentioned in the BOQ.
- 4- All the item quantities should be apply INCOTERM 2010 DDP (Delivery Duty Paid) to the mentioned locations.
- 5- Our organization is not bound to contract with one company and can split the award between one or more companies.
- 6-The company must submit approved site visit form and to be added to bid documents.

ملاحظات:

- 1- يجب الموافقة على جميع الفقرات من قبل مهندس الموقع لمنظمتنا.
- 2- يجب على المقاول تنظيف الموقع من جميع المواد المتبقية والمخلفات المتبقية بعد الانتهاء من العمل ونقله إلى الموقع المحدد من قبل الإدارة المحلية.
- 3- منظمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
- 4- جميع كميات المواد يجب أن يكون (التسليم واجب مدفوعة) إلى المواقع المذكورة.
- 5- المنظمة ليست ملزمة بأن تتعاقد مع شركة واحدة. و يمكن تجزئة العطاء بين أكثر من شركة
6. يجب على الشركة تقديم استمارة زيارة الموقع موقعة ومعتمدة من قبل المهندس المشرف للمنظمة و يجب إرفاقها مع مستندات العطاء المقدم.

Name of Signatory: _____

Title of Signatory: _____

Name of Bidder: _____

Signature & stamp: _____

Date of Signing: _____