

FINANCIAL OFFER 2: General Maintenance in Twhinya Camp in Northeast Syria.

العرض المالي 2: صيانة عامة لمخيم الطوحيانية في شمال شرق سوريا

Sunshade for visitors in TWH camp						
#	Item description	Unit	Qty	Unit Price (USD)	Total Price (USD)	Sample Required
1	Sunshade: Supply Material and implementing sunshade using steel frame (rectangular pipe) 8cmX5cm, 2mm thickness for the main structure and (rectangular pipe) 4cmX8cm, 1.8mm thickness for riling and the structure should be supported with steel rectangular pipe 8cmX8cm. 1.8mm thickness fixed with concrete (1:2:4) by dimension (0.3x0.3x0.5) m, and the item includes supply and extend zinc sheet, 0.7mm thick. the work should do according to the technical instructions & engineering drawings, including paint all the frame with anti-rust paint and two layer of oil paint, with all necessary needs to complete the work according to the site engineer instructions.	M ²	35			
2	Concrete Works: - Supply and cast reinforced concrete (1:2:4), width, with 15 cm thickness for the floor using BRC mesh (15X15)cm and 6mm thick., the price includes laying thick nylon under the concrete, watering, shuttering, curing and framework by plywood are included as requirements. The concrete surface should be smoothened. with all necessary needs to complete the work, all the work should be done according to the site engineer instructions.	M3	5			
Total Cost (USD)						
Maintenance of road lighting poles in TWH camp						
#	Item description	Unit	Qty	Unit Price (USD)	Total Price (USD)	Sample Required
1	Maintenance of the lighting poles by supply all tools, equipment and workers and crane to installation of a 150W solar power device on lampposts (6m height). All parts of the device are within it (battery, electrical regulator, charging board, Sensitive to sunlight to adjust the automation process). the device includes the advantage of having a remote control to adjust it, Work involves removing old and damaged devices and handing them over to the Blumont team and the work involves replacing the metal arms and installation and everything is required to install and operate the device, all the works should be done according to the site engineer instructions.	No	90			YES
Total Cost (USD)						
Road Maintenance						
#	Item description	Unit	Qty	Unit Price (USD)	Total Price (USD)	Sample Required
1	Maintenance of the roads in TWH camp by leveling the roads as needed and supplying and spread crush stone on the road, using equivalent machines needed (grader, roller, water tank, front loader "shovel"etc.) and labors the spreading of crushed stone layer at least 12 cm thick as needed, the price includes watering the site with good compacting, and remove the rubble and debris out of the camp to a location identified by the local authority, all the works should be done according to the site engineer instructions.	M3	1300			
2	Supply materials, tools and manpower to excavate and extend Iron pipe dia. 8 inch, with thick not less 4 mm, within the cross point of the roads, in the locations that idetified by site engineer within the camp site, the price includes casting sides of the pipe and the roof with concrete 350kg/m ³ reinforced with BRC (15x15)cm, 6mm thick, And implement a cement funnel on the entrance and exit of the iron pipe and laying one layer of crush stone not less than 7cm over the concrete all the work to be done according to the drawing and instructions of the site engineer	ML	80			
Total Cost (USD)						
Grand Total (USD)						

NOTES:

- 1- All the items should be approved by our organization's site engineer.
- 2- The contractor should clean the site from all remenant and remaining materials after completing the work to the identified location by Local Administration.
- 3- Our organization is not bound to buy the whole quantity mentioned in the BOQ.
- 4- All the item quantities should be apply INCOTERM 2010 DDP (Delivery Duty Paid) to the mentioned locations.
- 5- Our organization is not bound to contract with one company and can split the award between one or more companies.
- 6-The company must submit approved site visit form and to be added to bid documents.

ملاحظات:

- 1- يجب الموافقة على جميع الفقرات من قبل مهندس الموقع لمنظمتنا.
- 2- يجب على المفاول تنظيف الموقع من جميع المواد المتبقية والمخلفات المتبقية بعد الانتهاء من العمل ونقله إلى الموقع المحدد من قبل الإدارة المحلية.
- 3- منظمتنا ليست ملزمة بشراء الكمية الكاملة المذكورة في جدول الكميات.
- 4- جميع كميات المواد يجب ان يكون (التسليم واجب مدفوعة) إلى المواقع المذكورة.
- 5- المنظمة ليست ملزمة بان تتعاقد مع شركة واحدة، و يمكن تجزئة العطاء بين أكثر من شركة
- 6 يجب على الشركة تقديم استمارة زيارة الموقع موقعة ومعتمدة من قبل المهندس المشرف للمنظمة و يجب ارفاقها مع مستندات العطاء المقدم.

Name of Signatory: _____

Title of Signatory: _____

Name of Bidder: _____

Signature & stamp:

Date of Signing: _____